

PUBLIC WORKS

COLUMBUS RD / HARMONT AVE INTERSECTION IMPROVEMENTS
Plain Twp, Ohio



Owner:
Stark County Engineer

Total Project Cost:
\$1.4 million

Completion Date:
2007

Project Description:
This project consisted of intersection improvements. This intersection had the 3rd highest accident frequency in the county with a combined traffic volume of only 9,000 vehicles daily. The existing roadway was stop sign controlled at the bottom of a 14% grade. The roadway was lowered to an 8% grade resulting in 15' cuts and extensive utility relocations. The intersection was slightly realigned to improve sight lines. The project also included the addition of turn lanes on all approaches, traffic signals, curbing, underdrain, and a drainage system with 1,000' of "off-site" trunk sewer to a private lake.